



## Space

23,227 Sq Ft (10,580 sq ft raised)  
42U APC AR3100 Cabinets



## Connectivity

Carriers Available: Cogent,  
Level3/Century Link  
Port Sizes up to 100GE  
Wave Enabled



## Security

CCURE Card Reader Access System  
24/7 Building Access  
Cameras monitoring and recording  
24/7  
Gated Facility – code required for  
entry



## Environment



VESDA air sampling smoke detection  
system

FM-200 Gas Tanks

Multiple 30-Ton CRAC Units

Dry-pipe pre-action sprinkler system



## Power

Six 500kVA UPS Units

Each UPS has 3 Battery Strings (40  
batteries each)

2000kW Caterpillar Generator

8,000 gallon diesel fuel main tank

Multiple PDUs on data center floor

