



## Space

3,144 Sq Ft (1,159 sq ft non-raised;  
1,985 sq ft raised)  
42U APC AR3100 Cabinets



## Connectivity

Carriers Available: Cogent, AT&T,  
MFS, Spectrum, Verizon,  
Windstream  
Port Sizes up to 100GE  
Wave Enabled



## Security

Pin Pad access  
Door Contact alarms  
Fenced facility with a gate



## Environment

VESDA Xtralis  
Fike Cheetah Fire Alarm System  
Fike Halon Clean Agent Zones Suppression  
Systems  
Multiple HVAC Units



## Power

One 50kVA UPS  
One Cummins-Onan 450kW generator  
with 2500 gallon diesel fuel  
storage tank with Veeder Root  
monitoring unit  
One 800 amp ATS

