



Space

48,627 Sq Ft (16,800 sq ft raised)
42U APC AR3100 Cabinets
Free WiFi
Custom Cages Available



Connectivity

Carriers Available: Cogent, AT&T,
Level 3, City of Pasadena
Port Sizes up to 400GE
Wave Enabled
Utility Computing Available



Security

CCURE Card Reader
Access System
Cameras monitoring and
recording 24/7
Card Access and Pin Code
required for access
to data center



Environment

Heat detectors, smoke heads, pre-action
sprinkler system, separate gas-tank
system
Multiple FM-200 and Inergen tanks
Vesda air sampling smoke detection system
Multiple HVAC Units



Power

Partially Solar Powered (Sun Green
Array)
Six 500kVA UPS units
Multiple “sealed” UPS batteries
Three 1500kW Caterpillar Diesel
Generators
6,000 gallon diesel fuel tank
Four Benjamin Electric ATS
Multiple PDUs

See Back for Floor Plan

